

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Deutsch Oil Company
Address: 8100 E. 22nd. St. N. Bldg. 600 Wichita, Ks. 67226
Phone: (316) 681-3567 Operator License #: 3180
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-22977-00-00
Lease Name: Gordner
Well Number: 1-11
Spot Location (OOQQ): SE NE NW
990 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 11 Twp. 25 S. R. 11 East West
County: Stafford
Date Well Completed: _____
Plugging Commenced: 3-10-08
Plugging Completed: 3-11-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	232'	None
				5-1/2"	3951'	2385'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.
Plugged off bottom with sand to 3400' and 5 sxs. cement. Cut casing loose @2385', pulled up to 630', pumped 10 sxs. gel & 50 sxs. cement, pulled up to 270', pumped 50 sxs. cement, pulled up to 40' and topped off with 20 sxs., 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2008

Name of Party Responsible for Plugging Fees: Deutsch Oil Company
State of Kansas County: Rice SS.

CONSERVATION DIVISION
WICHITA, KS

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 25th day of March, 2008

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PJT