

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Contential Energy
Address: P.O. Box 918 Garden City, Ks. 67846
Phone: (620) 271-1264 Operator License #: 5317
Type of Well: Oil Gas KCCPKT per CP-1 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-145-21246-00-01
Lease Name: Keeley
Well Number: 1
Spot Location (OOQQ): _____ C _____ NE _____ NE
660 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 20 Twp. 21 S. R. 15 East West
County: Pawnee
Date Well Completed: _____
Plugging Commenced: 2-27-08
Plugging Completed: 2-28-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	940'	None
				4-1/2"	2025'	1660'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 1850' & 4 sxs cement. Cut casing loose @1660', pulled up to 932', pumped 10 sxs. gel & 50 sxs. cement. Pulled up to 400', pumped 40 sxs cement, pulled up to 40', topped off with 20 sxs cement, 60/40 pos, 4% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 26 2008

Name of Party Responsible for Plugging Fees: Continental Energy

CONSERVATION DIVISION
WICHITA, KS

State of Kansas County: Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 25th day of March 2008

Irene Herzberg
Notary Public

My Commission Expires: _____

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKK