

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD
K.A.R. 82-3-117

Lease Operator: Herman L. Loeb
 Address: P.O. Box 838 Lawrenceville IL, 62439
 Phone: (618) 943-2227 Operator License #: 3273
 Type of Well: SWD Docket #: E-26920
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 3/20/08 (Date)
 by: Richard Williams (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Cedar Hills Depth to Top: 2610' Bottom: 2650' T.D. 2760'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-199-20218-00-00
 Lease Name: Kuder
 Well Number: 1-29 KCC PKT Per RBDMs
 Spot Location (QQQQ): 130' W of - SW - SE - SW
330 Feet from North / South Section Line
1520 Feet from East / West Section Line
 Sec. 29 Twp. 15 S. R. 41 East West
 County: Wallace
 Date Well Completed: NA
 Plugging Commenced: 3/20/08
 Plugging Completed: 3/21/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	371'	0
				5 1/2"	2760'	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU Cheyenne Well Service. Run 2 7/8" tbg to 2540'. Mix and pump 125 sxs cement. Lay down tbg to 1330'. Circulate cement to surface w/ 110 more sxs 60/40 4%. Lay down tbg. Fill 5 1/2" to surface w. 25 more sxs. Hook up to 8 5/8" and pump 10 sxs, pressured test to 500#.
 RDMO Allied and Cheyenne.

Name of Plugging Contractor: Eastern Colorado Well Service LLC License # 32997 RECEIVED
Cheyenne Well Service License # 6454 KANSAS CORPORATION COMMISSION

Address: Box 384, Ness City Ks, 67560-0384 **MAR 25 2008**
 Name of Party Responsible for Plugging Fees: Herman L. Loeb
 State of Kansas County, Wallace, ss. CONSERVATION DIVISION WICHITA, KS

Alan Vertel (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Alan Vertel
 (Address) 509 W Cedar Medicine Lodge, KS 67104
 SUBSCRIBED and SWORN TO before me this 24 day of March, 2008.
Glenda Morrison My Commission Expires: 11/30/10
 Notary Public

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202