

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC
Address: P.O.Box 399 Garden City, Ks 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: oil Docket #: NA
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2-11-08 (Date)
by: Steve Durrant District One (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3605' Bottom: 3672' T.D. _____
Simpson Depth to Top: 3859' Bottom: 3862' T.D. 3895'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 185-21,677 - 00 - 00
Lease Name: Estes
Well Number: # 2
Spot Location (QQQQ): C - NE - Sw - SE
990' Feet from North / South Section Line
1650' Feet from East / West Section Line
Sec. 8 Twp. 22s S. R. 14 East West
County: Stafford
Date Well Completed: 11-30-1982
Plugging Commenced: 2-29-2008
Plugging Completed: 3-3-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	330'	Surface	8-5/8"	330'	None
	Production	3891'	Surface	5-1/2"	3891'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg to 1250' Spot 50 bbls mud & pump 50 sk pill w/ 100#s hulls, 4% CC, displace w/ 3-1/2 bbls wtr, on 2-29-08, pull tbg,
3-3-08 tagged cement w/ tbg, @ 744' pull tbg, perf. @ 662'-663' 4 shots, ran tbg, to 660', mix 450 sks 60/40 poz 4% gel
circulate cement to surface, pull tbg, top off csg, rig down,

Name of Plugging Contractor: Allied Cementing Co, License #: 99996 **RECEIVED**
Address: P.O. box 31 Russell Ks, 67665 **KANSAS CORPORATION COMMISSION**
MAR 24 2008

Name of Party Responsible for Plugging Fees: American Warrior INC **CONSERVATION DIVISION**
State of Kansas County, Finney, ss. **WICHITA, KS**

Kevin wiles Sr, Production Supt. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

ERICA KUHLMEIER
Notary Public - State of Kansas
My Appt. Expires 09-12-09

(Signature) _____
(Address) P.O.Box 399 Garden City, Ks 67846

SUBSCRIBED and SWORN TO before me this 19th day of March, 2008
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT