

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC
Address: P.O.Box 399 Garden City, Ks 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: oil Docket #: NA
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 2-11-08 (Date)
by: Steve Durrant District One (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3866' Bottom: 3875' T.D. 3875'
Depth to Top: _____ Bottom: _____ T.D. _____
Simpson Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 185-21,033 -00 -00
Lease Name: Estes
Well Number: # 1
Spot Location (QQQQ): C - SE - NW - SE
1650' Feet from North / South Section Line
1650' Feet from East / West Section Line
Sec. 8 Twp. 22s S. R. 14 East West
County: Stafford
Date Well Completed: 4-7-1980
Plugging Commenced: 2-26-08
Plugging Completed: 2-27-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	291'	Surface	8-5/8"	291	None
	Production	3866'	Surface	5-1/2"	3866'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 3615' w/ 5 sks cement on top, perf @ 880' ran tbg to 890' mix 275 sks 60/40 poz 4% gel, lost returns, hookup to backside,
mix 50 sks cem, to 500#s, pull tbg hook up to 5-1/2" csg, mix 110 sks cem, press to 800#S unhook.
5-1/2" csg full to surface, rig down,

99996 KCC PKT RECEIVED

Name of Plugging Contractor: Allied Cementing Co. License #: ID # 48-6727660 KANSAS CORPORATION COMMISSION

Address: P.O. box 31 Russell Ks, 67665 **MAR 24 2008**

Name of Party Responsible for Plugging Fees: American Warrior INC CONSERVATION DIVISION

State of Kansas County, Finney, ss. WICHITA, KS

Kevin wiles Sr, Production Supt. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

ERICA KUHLMEIER
Notary Public - State of Kansas
My Appt. Expires 09-12-09

(Signature) [Signature]
(Address) P.O.Box 399 Garden City, Ks 67846

SUBSCRIBED and SWORN TO before me this 19th day of MARCH, 2008
[Signature] My Commission Expires: 091209
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT