

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R & B Oil & Gas, Inc.
 Address: PO Box 195, Attica, KS 67009
 Phone: (620) 254-7251 Operator License #: 31191
 Type of Well: Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Doug Louis (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Stalnaker Depth to Top: 3720 Bottom: 3792 T.D. 3828
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-077-21494-00-00
 Lease Name: Gill A
 Well Number: 2 *KCC PLT per RBDm*
 Spot Location (QQQQ): 85'S + 140' W of - NE - SW
1895 Feet from North / South Section Line
1840 Feet from East / West Section Line
 Sec. 20 Twp. 32 S. R. 8 East West
 County: Harper
 Date Well Completed: 10-21-04
 Plugging Commenced: 1-25-08
 Plugging Completed: 1-30-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	239	
Stalnaker	Gas	3720	3792	4 1/2	3828	2840

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Sand at 3660', bailed 4 sacks cement, dug cellar and pit, unpacked casing head, set floor, pulled slips, had 26" stretch, cut surface off 4' below ground, ripped casing at 2840', pipe came free, pulled casing up to 1300', pumped 35 sacks 100# hulls, pulled to 750', pumped 35 sacks 100# hulls, pulled to 300', circulated with 115 sacks, pulled rest of casing.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925 **MAR 20 2008**
 Address: 190 US Highway 56, Ellinwood, KS 67526 CONSERVATION DIVISION
 Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc. WICHITA, KS
 State of Kansas County, Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Randy Newberry
 (Address) PO Box 195, Attica, KS 67009



SUBSCRIBED and SWORN TO before me this 19th day of March, 2008
Jane Swingle My Commission Expires: 1-6-2011
 Notary Public, Jane Swingle

