

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R & B Oil & Gas, Inc.
 Address: PO Box 195, Attica, KS 67009
 Phone: (620) 254-7251 Operator License #: 31191
 Type of Well: Oil/Gas KCCP/KR/AM CP2/B3 Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Doug Louis (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 4404 Bottom: 4412 T.D. 4840
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-077-21582-0000
 Lease Name: McDaniel
 Well Number: 1
 Spot Location (QQQQ): _____ - W2 - SW - SE
660 Feet from North / South Section Line
2310 Feet from East / West Section Line
 Sec. 11 Twp. 32 S. R. 9 East West
 County: Harper
 Date Well Completed: 5-22-07
 Plugging Commenced: 1-23-08
 Plugging Completed: 1-25-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	266	
Miss	Oil	4404	4412	5 1/2	4838	3850

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4260', bailed 5 sacks cement, dug cellar, unpacked casing head, set floor, pulled slips, had 30" stretch, ripped casing at 3850', worked pipe free, pulled casing up to 1400', pumped 35 sacks, pulled to 800', pumped 35 sacks, pulled to 320', circulated with 160 sacks, pulled casing out.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
 Address: 190 US Highway 56, Ellinwood, KS 67526
 Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.
 State of Kansas County, Harper, ss.
 RECEIVED
 KANSAS CORPORATION COMMISSION
 MAR 20 2008
 CONSERVATION DIVISION
 WICHITA, KS


Randy Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Randy Newberry

(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED and SWORN TO before me this 19th day of March, 2008

Jane Swingle My Commission Expires: 1-6-2011
 Notary Public, Jane Swingle



QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1781

Date	1-25-08	Sec.	11	Twp.	32	Range	9	Called Out	8 AM	On Location	8 AM	Job Start	9 AM	Finish	12 noon		
Lease	Mc DANIEL	Well No.	1	Location	W/2 SW SE			County	HARPE+	State	K.S.						
Contractor	QWS				Owner	R+B OIL + GAS INC.											
Type Job	OHP				To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.												
Hole Size	7 7/8	T.D.	4838														
Csg.	5 1/2	Depth	Charge To R+B														
Tbg. Size		Depth	Street PO Box 195														
Drill Pipe		Depth	City ATTICA										State		K.S. 67009		
Tool		Depth	The above was done to satisfaction and supervision of owner agent or contractor.														
Cement Left in Csg.		Shoe Joint															
Press Max.		Minimum															
Meas Line		Displace															
Perf.														CEMENT			
EQUIPMENT		Amount Ordered	230 SKS 60/40 49% 4 Hulls														
Pumptrk	6	No.	Cementer	DEAN											Consisting of		
			Helper														
Bulktrk	4	No.	Driver	RICH											Common	138 @ 11.05	1524.45
			Driver												Poz. Mix	92 @ 6.10	561.20
Bulktrk		No.	Driver												Gel.	10 @ 17.00	170.00
			Driver												Chloride		
JOB SERVICES & REMARKS																	
Pumptrk Charge	PTA		700.00														
Mileage	25 mi @ 6.00		156.00														
Footage																	
		Total	856.00														
Remarks:	2 Hulls 35 SKS at 1400'																
	2 Hulls 35 SKS at 800'																
	civ. well at 320' with 160 SKS																
		Handling	244 @ 1.90														
		Mileage	89 per sk per mile														
		Sub Total															
		Total															
		Floating Equipment & Plugs															
		Squeeze Manifold															
		Rotating Head															
RECEIVED KANSAS CORPORATION COMMISSION MAR 20 2008 CONSERVATION DIVISION WICHITA, KS																	
		Tax	220.36														
		Discount	(416.00)														
		Total Charge	3962.06														
X Signature	