

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R & B Oil & Gas, Inc.

Address: PO Box 195, Attica, KS 67009

Phone: (620) 254-7251 Operator License #: 31191

Type of Well: gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Doug Louis (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Topeka Depth to Top: 2938 Bottom: 2940 T.D. 2938

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-077-21439-00-00

Lease Name: Bertholf

Well Number: B1

Spot Location (QQQ): 115'S + 130' W of - 8 SW - NE - SW

1865 Feet from North / South Section Line

1850 Feet from East / West Section Line

Sec. 18 Twp. 31 S. R. 8 East West

County: Harper

Date Well Completed: 10-16-02

Plugging Commenced: 2-1-08

Plugging Completed: 2-4-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	241	
Topeka	Gas	2938	2940	4 1/2	2930	2210

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 2860', bailed 4 sacks cement, ripped casing at 2430', worked pipe, ripped casing at 2210', came free, pulled casing up to 1450', pumped 35 sacks, pulled to 900', pumped 35 sacks, pulled to 290', circulated with 90 sacks, pulled rest of casing, emptied pit, cleaned up location.


Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: R & B Oil & Gas Inc

State of Kansas County, Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Randy Newberry

(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED and SWORN TO before me this 19th day of March, 2008

Jane Swingle My Commission Expires: 1-6-2011
Notary Public Jane Swingle

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 20 2008

CONSERVATION DIVISION
WICHITA, KS

KCC PLOT
Per CP 213

PH

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1784

Date	2-4-08	Sec.	18	Twp.	31	Range	8	Called Out		On Location		Job Start	10:30	Finish	12:00	
Lease	Bertholt	Well No.	B1	Location	5 1/2 N West Into			Harper	County	KS	State					
Contractor	Quality Well Service							Owner	from Africa							
Type Job	Plug								To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.							
Hole Size		T.D.														
Csg.	4 1/2	Depth							Charge To	R + B oil + Gas						
Tbg. Size		Depth							Street							
Drill Pipe		Depth							City State							
Tool		Depth							The above was done to satisfaction and supervision of owner agent or contractor.							
Cement Left in Csg.		Shoe Joint														
Press Max.		Minimum														
Meas Line		Displace							CEMENT							
Perf.																
EQUIPMENT								Amount Ordered	160 sks 60/40 4%							
Pumptrk	6	No.	Cementer	Duce				Helper								
Bulktrk	4	No.	Driver	Rich				Driver								
Bulktrk		No.	Driver					Driver								
JOB SERVICES & REMARKS								Consisting of								
Pumptrk Charge	PTA		700 ⁰⁰					Common	96 @ 12 ⁰⁰		1152 ⁰⁰					
Mileage	30 miles @ 6 ⁰⁰		180 ⁰⁰					Poz. Mix	64 @ 6 ⁵⁰		416 ⁰⁰					
Footage								Gel.	7 @ 18 ⁰⁰		126 ⁰⁰					
			Total 880 ⁰⁰					Chloride								
								Hulls	200 # @ 25 ⁰⁰		50 ⁰⁰					
								Salt								
								Flowseal								
Remarks:	1 st 1450 pumped 35sks 700 # Hulls															
	2 nd 900 pumped 35sks 100 # Hulls															
	3 rd circulated cement from 290 with 90 sks to surface.															
	Sales Tax															
	Handling 169 @ 2 ⁰⁰															
	Mileage 8¢ per sk per mile															
	Sub Total															
	Total															
	Floating Equipment & Plugs															
	Squeeze Manifold															
	Rotating Head															
	Tax															
	Discount															
	Total Charge															

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 20 2008
CONSERVATION DIVISION
WICHITA, KS

X Signature Daniel Brady

[Handwritten initials]