

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Berexco, Inc.
Address: PO Box 723 Hays, KS 67601
Phone: (785) 628-6101 Operator License #: 5363
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-2-07 (Date)
by: MARVIN MILLS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
TOP Depth to Top: 3659 Bottom: 63 T.D. 3991
L-KC Depth to Top: 3810 Bottom: 3925 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-20773-00-00
Lease Name: LAW B
Well Number: 6
Spot Location (QQQQ): S/2 - NE - NE -
4290 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 34 Twp. 9 S. R. 23 East West
County: GRAHAM
Date Well Completed: 9-75
Plugging Commenced: 11-1-07
Plugging Completed: 11-2-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
TOP	OIL, WATER	0	182	8-5/8	9/75	---
L-KC	OIL	0	3991	4-1/2	9/75	----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


RIG UP PERFTECH SHOOT 2 HOLES EACH AT 2380, 1950, 1240. RUN OPEN END TBG TO 3575'. RIG UP ALLIED CEMENTING MIX 65 SXS 60/40 POZ 4% GEL W/ 300# HULLS IN LAST 55 SXS
PULL TBG TO 2585' MIX 65 SXS 60/40 PAZ 4% GEL W/ 200# HULLS. PULL TBG TO 1590' CIRC CMT TO SURFACE INSIDE 4-1/2 CSG
W/ 100 SXS 60/40 POZ 4% GEL AND 200# HULLS. PULL TBG OUT OF HOLE. TIE ONTO 4-1/2 CSG MIX 35 SXS CMT, PRESS TO 300# - SHUT IN 4-1/2
W/ 250# PRESS HOOK UP TO 8-5/8 . MIX 60 SXS CMT W/ 100# HULLS PRESS TO 300# SHUT IN ANNULUS @ 150#

Name of Plugging Contractor: Berexco, Inc. License #: 5363
Address: PO Box 723 Hays, KS 67601
Name of Party Responsible for Plugging Fees: Dennis Kirmer Berexco, Inc
State of KS County, ELLIS, ss.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 31 2008

(Employee of Operator) or (Operator) on above-described well (being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Dennis Kirmer
(Address) PO Box 723 Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 27 day of March, 20 08
Shanna Miller My Commission Expires: 9-19-09
Notary Public