

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Exxon Mobil Oil Corporation
Address: PO Box 4358 Houston TX 77210
Phone: 713 431 1936 Operator License #: 5208
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2-1-08 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Chase Depth to Top: 2499' Bottom: 2815' T.C. 2815'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-189-00186-00-00
Lease Name: Barnard
Well Number: 1
Spot Location (QQQQ): C-NE-NE-SW
2310 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 32 Twp. 31 S. R. 35 East West
County: Stevens
Date Well Completed: 5-14-50
Plugging Commenced: 2-4-08
Plugging Completed: 2-6-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4	542	—
				7	2512	—
				5 1/2 liner	2499-2815	—

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Top of junk 1500. Ran 2 3/8 to 1500. Mixed 100 lb. hulls & 40 sx cmt. plug from 1500 to 1300, mud to 1000, mixed 350 lb. hulls @ casing leak, then circ. hole w/mud. Pull 172,000 on 7", no stretch. Ran 2 3/8 to 570. Mixed 40 sx 570 to 370, 8 sx cmt. 40 to 0 Cut 10 3/4 & 7 + capped 10 3/4 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: EXXON MOBIL
State of KANSAS County, STEVENS, ss.

RICHARD B LEWIS (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC, State of Kansas
DORETTA L. DELAY
My Appt. Exp. 12-27-08

(Signature) R B Lewis 3/17/08
(Address) 200 W 4th HUGOTON KS 67951

SUBSCRIBED and SWORN TO before me this 22 day of Feb., 20 08

Doretta L. Delay
Notary Public

My Commission Expires: 12-27-08 RECEIVED
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Permitting
MAR 24 2008

MAR 31 2008

regulatory contact: Jacqueline Davis 3/28/08 281-654-1913

CONSERVATION DIVISION
WICHITA, KS