

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Lease Operator: BP America Production Company
Address: P.O. Box 3092, Rm 6.121, Houston, TX 77253
Phone: 281.366.4395 Operator License #: 5952
Type of Well: Gas Docket #:
The plugging proposal was approved on: 9/5/2006
by: Eric Maclaren
Is ACO-1 filed? Yes No
Producing Formation(s): Chase Depth to Top: 2392 Bottom: 2590

API Number: 15- 129-00503 -00-00
Lease Name: Sparks Gas Unit
Well Number: 1
Spot Location (QQQQ): NE NE NE SW
2640 Feet from North / South Section Line
2640 Feet from East / West Section Line
Sec. 9 Twp. 31 S. R. 39 East West
County: Morton
Date Well Completed: 11/23/1951
Plugging Commenced: 4/3/2007
Plugging Completed: 4/3/2007

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put in, Pulled out. Rows include SURFACE CASING, LINER, and PRODUCTION CASING.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set CTBP @ 2290' w/2 sxs cement on top. Set CTBP @ 700'; Perf circulating holes at 650'; Mix & pump 235 sxs cement down 4.5" csg & circulate cement up annulus between 7" & 10.75" csg, leaving 4.5" csg & annulus full of cement from GL to 650'; Connect to annulus between 4.5" & 7" & pump 1/4 bbl cement to fill annulus & pressure to 600 psi; Cut off & cap csg 5' below GL; Restore location; Mixed class C cement @ 14.8 ppg w/1.32 cuft/sk yield.

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P. O. Box 1706, Duncan, OK 73534


Name of Party Responsible for Plugging Fees: BP America Production Company

State of Texas County, Harris, ss.

DeAnn Snyers (Employee of Operator) or (Operator) on above-described well as filed and the same are true and correct, so help me God.

(Signature) DeAnn Snyers

(Address) P.O. Box 3092, Rm 6.121, Houston, TX 77253-3092



SUBSCRIBED and SWORN TO before me this 24th day of March, 2008. Suzanne M. Jones, Notary Public, My Commission Expires: 1-11-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED KANSAS CORPORATION COMMISSION

MAR 27 2008

CONSERVATION DIVISION WICHITA, KS

Handwritten initials/signature at bottom right.