

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Lease Operator: BP America Production Company

API Number: 15- 055-20255 -00-00

Address: P.O. Box 3092, Rm 6.121, Houston, TX 77253

Lease Name: J. J. Meyer G. U.

Phone: 281.366.4395 Operator License #: 5952

Well Number: 2

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): - W2 - E2 - SW

The plugging proposal was approved on: 7/11/2006 (Date)

1320 Feet from North / South Section Line

1700 Feet from East / West Section Line

by: Steve Durrant (KCC District Agent's Name)

Sec. 3 Twp. 23 S. R. 33 East West

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

County: Finney

Producing Formation(s): List All (If needed attach another sheet)

Date Well Completed: 4/9/1977

Chase Depth to Top: 2503 Bottom: T.D. 2640

Plugging Commenced: 4/25/2007

Depth to Top: Bottom: T.D.

Plugging Completed: 4/25/2007

Depth to Top: Bottom: T.D.

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put in, Pulled out. Rows include SURFACE CASING and PRODUCTION CASING.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set CTBP @ 2450' w/2 sxs cement on top (plug was set on 10/20/06); Mix & pump 125 sxs class "C" cement to fill csg from GL to csg leak at 1088'; Use 75 lbs of cottonseed hulls in the lead part of cement; fill 8 5/8 x 5 1/2 annulus w/7 sxs cement; Cut off and cap csg 5' below GL; Restore the location; Cement was mixed at 14.8 ppg with 1.32 cuft/sk yield.

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P. O. Box 1706, Duncan, OK 73534

Name of Party Responsible for Plugging Fees: BP America Production Company


State of Texas County, Harris, ss.

DeAnn Snyers (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) DeAnn Snyers

(Address) P.O. Box 3092, Rm 6.121, Houston, TX 77253-3092



SUBSCRIBED and SWORN TO before me this 24th day of March, 20 08

Suzanne M. Jones Notary Public My Commission Expires: 1-11-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED KANSAS CORPORATION COMMISSION

MAR 27 2008

CONSERVATION DIVISION WICHITA, KS

PKT