

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: PINTAIL PETROLEUM, LTD.  
Address: 225 N. MARKET, SUITE 300, WICHITA, KS 67202  
Phone: (316) 263-2243 Operator License #: 5086  
Type of Well: OIL Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 6/18/2007 (Date)  
by: MICHAEL MAIER (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
MISSISSIPPI Depth to Top: 4546 Bottom: 4552 T.D. 4575  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 135-22095-00-00  
Lease Name: BREIT  
Well Number: 1  
Spot Location (QQQQ): NW - SW - NE - SE  
1815 Feet from  North /  South Section Line  
1155 Feet from  East /  West Section Line  
Sec. 8 Twp. 16 S. R. 25  East  West  
County: NESS  
Date Well Completed: 10/12/1982  
Plugging Commenced: 6/18/2007  
Plugging Completed: 6/18/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
MISSISSIPPI	OIL	340'	SURFACE	8-5/8"	340'	NONE
		4574'	PRODUCTION	5-1/2"	4574'	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

LEFT 1470' TUBING IN HOLE. HAD A CASING BREAK IN. WASHED OVER TUBING AND GOT TO 3100'. NO ALT 2 CEMENT. RAN TUBING TO 3100' & PUMPED 35 SX COMMON CMT WITH 3% CC. PULLED TUBING TO 1350' & PUMPED 60SX COMMON CMT WITH 3%CC. WAITED 1 1/2 HRS. PRESSURED CASING TO 500' & HELD. PERF @ 1050'. TIED ONTO CASING AND PUMPED 170 SX CMT. DID NOT CIRC. MAX PRESSURE 900#. SI PRESSURE 500#. TIED ONTO BACKSIDE & PUMPED 100SX CMT. CMT CAME UP 12' FROM WELL HEAD.

**RECEIVED**  
**KANSAS CORPORATION COMMISSION**

Name of Plugging Contractor: WHITETAIL CRUDE License #: 31627  
Address: N HWY 283, PO BOX 544, NESS CITY, KS 67560  
Name of Party Responsible for Plugging Fees: PINTAIL PETROLEUM, LTD.  
State of KANSAS County, SEDGWICK, ss.  
**CONSERVATION DIVISION**  
**WICHITA, KS**

BETH A. ISERN (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Beth A. Isern  
(Address) 225 N. MARKET, SUITE 300. WICHITA, KS 67202

SUBSCRIBED and SWORN TO before me this 1st day of April, 2008  
Susan Utterback My Commission Expires: 9/18/2010  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas

