

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD

K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION

APR 01 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mull Drilling Company, Inc.

Address: P.O. Box 2758 Wichita, Kansas 67201-2758

Phone: (316) 264-6366 #13 Operator License #: 5144

Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 101-22074-00-00

Lease Name: Johnson "A"

Well Number: 1-8

Spot Location (QQQQ): NW - SW - SE - SE
335 Feet from North / South Section Line

1240 Feet from East / West Section Line

Sec. 8 Twp. 17 S. R. 27 East West

County: Lane County, Kansas

Date Well Completed: 02-17-08

Plugging Commenced: 02-18-08

Plugging Completed: 02-18-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	207'	8 5/8"	196'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug: 2160' w/50 sacks cement through drillpipe

2nd Plug: 1260' w/80

3rd Plug: 630' w/50

4th Plug: 240' w/40 Top Plug: 60' w/20 Rathole w/15


Name of Plugging Contractor: Duke Drilling Co., Inc. License #: 5929

Address: P.O. Box 823 Great Bend, Kansas 67530

Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Mark A. Shreve, President/COO (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) _____

(Address) P.O. Box 2758, Wichita KS 67201-2758

SUBSCRIBED and SWORN TO before me this 31st day of March, 20 08

Tannis L. Tritt My Commission Expires: 3-26-2011
Notary Public

Handwritten initials/signature

ALLIED CEMENTING CO., INC.

30709

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

APR 01 2008 SERVICE POINT:

Ness Cty

CONSERVATION DIVISION

DATE <u>2-18-08</u>	SEC. <u>8</u>	TWP. <u>1N</u>	RANGE <u>28</u>	WICHITA, KS CALLED OUT <u>5:00 AM</u>	ON LOCATION <u>9:50 AM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>12:00 PM</u>
LEASE <u>Johnson</u>	WELL # <u>1-8</u>	LOCATION <u>Penn Dennis 1/2 E, 35, 1/4 W, 5/8</u>			COUNTY <u>Lane</u>	STATE <u>Ks</u>	
OLD OR <u>(NEW)</u> (Circle one)							

CONTRACTOR Duke #4

TYPE OF JOB Rotary plug

HOLE SIZE 7 1/2" T.D. 4675'

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2" DEPTH 2160'

TOOL _____ DEPTH _____

PRES. MAX 2000 MINIMUM 0

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT Freshwater + Rig mud

EQUIPMENT _____

PUMP TRUCK CEMENTER Rich H.

181 HELPER David J.

BULK TRUCK _____

357 DRIVER Gailen D.

BULK TRUCK _____

_____ DRIVER _____

OWNER Mull drilling

CEMENT

AMOUNT ORDERED 255 SX 60/40 4% 4# Flo-seal

COMMON	<u>153</u>	@	<u>12.30</u>	<u>1881.90</u>
POZMIX	<u>102</u>	@	<u>6.85</u>	<u>698.70</u>
GEL	<u>10</u>	@	<u>18.40</u>	<u>184.00</u>
CHLORIDE		@		
ASC		@		
<u>Flo-seal 64</u>		@	<u>2.20</u>	<u>140.80</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>268</u>	@	<u>2.10</u>	<u>562.80</u>
MILEAGE	<u>47.9</u>	@	<u>2.68</u>	<u>1133.64</u>
				TOTAL <u>4601.84</u>

REMARKS:

2160' - 50 SX

1260' - 80 SX

630' - 50 SX

240' - 40 SX

60' - 20 SX Cement did Circulate

Rotable - 15 SX

255 SX 60/40 4% 4# Flo-seal

CHARGE TO: Mull drilling

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB 2160'

PUMP TRUCK CHARGE _____ 1055.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 47 @ 7.00 329.00

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 1384.00

PLUG & FLOAT EQUIPMENT

1- wooden plug 67.00

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL 67.00

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Rich Wheeler

x Rich Wheeler
PRINTED NAME