

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD**

RECEIVED
CORPORATION COMMISSION
APR 01 2008
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

K.A.R. 82-3-117

Lease Operator: Edgewood Land & Cattle Comp. Inc.
 Address: 618 Westchester Dr., Andover, KS 67002
 Phone: (316) 733-2248 Operator License #: 30471
 Type of Well: Oil DH KCC PKT per CP 2/3 Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 2/27/08 (Date)
 by: Mike Heffern (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Bartlesville Depth to Top: 2290 Bottom: 2366 T.D. 2375
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 073-24068-0000
 Lease Name: Browning
 Well Number: 29
 Spot Location (QQQQ): SW - NE - SW -
1650 Feet from North / South Section Line
1470 Feet from East / West Section Line
 Sec. 20 Twp. 22 S. R. 10 East West
 County: Greenwood
 Date Well Completed: 12/27/07
 Plugging Commenced: 2/27/08
 Plugging Completed: 2/27/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Bartlesville		surface	200'	8 5/8"	12/6/07	none
		surface	2375'	5 1/2"	12/11/07	pulled out 2049'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Shot off casing @ 2049' -- pulled casing from hole--ran 2 7/8" tubing to 2345'--spotted 60 sks. 60/40 pozmix--spotted 25sk of cement @ 961'
pulled up and placed 115 sk. of cement from 300' to ground level.

KCC PKT per CP 2/3


Name of Plugging Contractor: consolidated Oil Well Service LLC License #: 33961
 Address: P.O. Box 884, Chanute, KS 66720

Name of Party Responsible for Plugging Fees: Edgewood Land & Cattle comp. Inc.
 State of Kansas County, Greenwood, ss.

Harry Patterson--Agent (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Harry Patterson
 (Address) 618 Westchester Dr., Andover, KS 67002

SUBSCRIBED and SWORN TO before me this 25TH day of March, 20 08
Jackie Disney My Commission Expires: 01-01-09
 Notary Public



CONSOLIDATED OIL WELL SERVICES, LLC
 P.O. BOX 884, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8876

TICKET NUMBER **13611**
 LOCATION Edgwood
 FOREMAN Kevin McCoy

TREATMENT REPORT & FIELD TICKET
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
2-27-08	2523	Browning #29				GW
CUSTOMER Edgewood Land & Cattle Co.		Glacier Well Service	TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 618 Westchester Dr.			445	Steve		
CITY Andover			441	Ed		
STATE KS	ZIP CODE 67002					
JOB TYPE <u>P.T.A.</u>	HOLE SIZE <u>7 7/8</u>	HOLE DEPTH <u>2375'</u>	CASING SIZE & WEIGHT			
CASING DEPTH	DRILL PIPE	TUBING <u>2 7/8 Euc</u>	OTHER			
SLURRY WEIGHT	SLURRY VOL. <u>50 BBL</u>	WATER gal/sk	CEMENT LEFT IN CASING			
DISPLACEMENT	DISPLACEMENT PSI	MIX PSI	RATE			
REMARKS: <u>Safety meeting. ON 2-23-08 Precision Well Perforator shot casing over @ 2049'</u> <u>Rig & Dril Co. Pulled casing. 2-27-08 Rig & Dril Co. Ran 2 7/8 Tubing (76 JTS) @ 2045'</u> <u>(5 1/2 casing left in bottom of hole 2049' - 2365') Rig up & 2 7/8 Tubing. Spot 60 500 Gal</u> <u>Formix Cement w/ 4% Gal, 2% Calc @ 2345'. Pull 44 JTS Tubing. Spot 25 500 Cement</u> <u>@ 961'. Pull 22 JTS Tubing. Spot Solid Cement Plug from 500' to Surface. Pull</u> <u>Remaining 10 JTS 2 7/8 Tubing. Top off hole w/ cement. Top Plug = 115 500 Cement.</u> <u>Job Complete. Rig down.</u>						

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405 N	1	PUMP CHARGE	875.00	875.00
5406	25	MILEAGE	3.48	87.25
1191	200 SRS	60/40 Formix Cement	10.00	2000.00
1118 A	690 "	Gal 4%	.16	110.40
1102	345 "	Calc 2%	.70	241.50
5407	8.6 TONS	Ton Mileage BULK TRUCK	MIC	300.00
RECEIVED KANSAS CORPORATION COMMISSION				
APR 01 2008				
CONSERVATION DIVISION WICHITA, KS				
			Sub Total	3781.15
			SALES TAX 6.3%	150.25
			ESTIMATED TOTAL	3931.40

AUTHORIZATION witnessed By Sale TITLE Edgewood Co. Rep. DATE _____

THANK YOU
 880453