

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20161-00-02  
Spot: SESW Sec/Twnshp/Rge: 4-27S-6W  
660 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: KING Well #: 3  
County: KINGMAN Total Vertical Depth: 4247 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	4247		135 SX
SURF	10.75	266		225 SX

138.03

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2008 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DIAMOND DICK SCHREM Company: BEAR PETROLEUM INC Phone: (316) 524-1225

Proposed Plugging Method: PER KCC RULES AND REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/28/2008 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

ON 12/5/2007 CASING WAS PERF @ 950' BY WIRELINE W/3 SHOT LOAD WITNESSED BY SVG. ON 1/28/08 TUBING WAS RAN INTO 2775' - 50 SXS OF CEMENT W/C.C. AND 150 LBS OF C.HULLS WAS SPOTTED. TUBING PULLED TO 955' - 50 SXS OF CEMENT WERE SPOTTED. CAME BACK AND TAGGED TOP OF CEMENT WITH WIRELINE @ 737', PRESSURED UP AND HELD 300 LBS. WENT BACK IN WITH WIRELINE PERFED AT 390'-391' CIRCULATED 250 SXS TO SURFACE. ON 1/29/08 CHECKED TOP PLUG, IT FELL BACK 121', INSIDE CASING, FELL BACK 24 FT ON BACK SIDE. ON 2-20-08 COPELAND CEMENT TOPPED OFF SURFACE WITH 32 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
2746	2770		

INVOICED

DATE 4-10-08  
INV. NO. 2008061500

RECEIVED  
KANSAS CORPORATION COMMISSION  
**APR 02 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENT CO., OUT OF BURTON, TICKET #32691 60/40 POS 4% GEL

Plugged through: TBG

District: 02

Signed B. J. Hope  
(TECHNICIAN)

*PK*