

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20783-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 20-18S-6W  
330 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: WOLF D J Well #: 1  
County: RICE Total Vertical Depth: 3380 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 360  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3379		175 SX
SURF	8.625	225		140 SX

109.85

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2008 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: MICHAEL WILSON Witness Type: NONE  
Date/Time Plugging Completed: 03/21/2008 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 2750' AND CAP WITH 4 SX'S CEMENT. CUT OFF CASING AT 1200' AND PULL TO 950' AND PUMP 35 SX'S CEMENT. PULL CASING TO 600' AND PUMP 35 SX'S CEMENT. PULL CASING TO 275' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT OF HOLE AND TOP OFF. USED 185 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3266	3269		
3262	3264		
3260	3262		
3030	3035		
2806	2809		

**INVOICED**  
DATE 4-10-08  
INV. NO. 2008061503

RECEIVED  
KANSAS CORPORATION COMMISSION  
**APR 02 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-33487.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)