

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20422-00-02
Spot: SENENW Sec/Twnshp/Rge: 19-9S-20W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: TURNER Well #: 6
County: ROOKS Total Vertical Depth: 3817 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3807	0	100 SX
SURF	8.625	283	0	200 SX

124.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2008 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8704

Proposed Plugging Method: Ordered 380 sxs 60/40 pozmix - 4% gel - 900# hulls - 12 sxs gel.
Perf Tech shot holes at 330' - 1030' - 1760' - 2200'.
Fluids 300'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2008 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 3642'. Rigged to tubing and pumped 60 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 3028' - pumped 12 sxs gel with 100# hulls mixed in.
Pulled tubing to 1869'. Rigged to tubing and pumped 155 sxs cement with 600# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 140 sxs to circulate cement out 8 5/8".
Shut in 8 5/8" - pumped 10 sxs cement.
Max. P.S.I. 250#. S.I.P. 0#. Blew stuffing out backside of head.

Perfs:

Top	Bot	Thru	Comments
3807	3817		ARBUCKLE

INVOICED
DATE 4-10-08
INV. NO. 2008061513

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 27 2008

Remarks: SWIFT SERVICES, INC.-TICKET #135000.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

MAR 25 2008

AMERICAN PETROFINA OF TEXAS #6 TURNER 19-9-20W
 RUSSELL, KANSAS SE NE NW
 CONTR GABBERT-JONES CTY ROOKS
 GEOL FRANCIS WHISLER FIELD GRA-ROOK
 E 2262 KB CM 3/7/72 CARD ISSUED 3/31/72 IP POT 45 BOPD NW NAT
 ARB 3807-17

API 15--163-20,422

SMP	TOPS	DEPTH	DATUM	
				8 5/8" 275/200sx; 5 1/2" 3807/100sx
SC	1765	+ 497		DST(1) 3808-17/30-30-30-30, 90' GIP, 150'
B SC	1805	+ 457		CL OIL, 180' M OIL, BHP 728-611#, FP
HEEB	3481	-1219		22-142#
TOR	3505	-1243		
LANS	3521	-1259		MICT, CO TO 3817 TD, P 45 BOPD NW NAT.
BKC	3741	-1479		
CHTY CONG	3781	-1519		NO LOG
SIMP SH	3796	-1534		
ARB	3805	-1543		
RTD	3817	-1555		

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS