

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21704-00-00
Spot: SENENW Sec/Twnshp/Rge: 10-15S-28W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ROBERTS "E" Well #: 1-10
County: GOVE Total Vertical Depth: 4320 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		

140.40

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/14/2008 3:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 03/14/2008 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 1941' w/25 sxs.
2nd. Plug at 905' w/100 sxs.
3rd. Plug at 260' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 4-10-08
INV. NO. 2008061524

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 28 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

PKT

MAR 26 2008