

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22208-00-00
Spot: NESESE Sec/Twnshp/Rge: 26-11S-17W
890 feet from S Section Line, 280 feet from E Section Line
Lease Name: MCCORD A Well #: 18
County: ELLIS Total Vertical Depth: 3664 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3664	0	w/250 sxs cmt
SURF	8.625	328	0	w/250 sxs cmt

119.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2008 10:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls - 12 sxs gel.
DV Tool at 1277' w/290 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2008 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 3317'. Rigged to tubing and pumped 12 sxs gel, followed with 60 sxs 60/40 pozmix with 350# hulls mixed in.
Pulled tubing to 1850' - pumped 185 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 30 sxs 60/40 pozmix.
Max. P.S.I. 400#. S.I.P. 400#.
Rigged to 8 5/8" - pumped 50 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3592	3594		

INVOICED

DATE 4-10-08
INV. NO. 2008061525

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 28 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #24750.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

MAR 26 2008

CITIES SERVICE COMPANY
 700 SUTTON PLACE BLDG.
 WICHITA, KS 67202

#18 MCCORD "A"

26-11-17W
 NE SE SE

CONTR PIONEER DRILLING

CTY ELLIS

GEOL _____

FIELD BEMIS-SHUTTS

2106 KB CM 4/28/81

CARD

ISSUED 6/11/81

IF P 25 BO & 335 BWPD

2101 GL

ARB 3592-3594

API 15-051-22,208

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
HEEB		3237	-1131
LANS		3285	-1179
ARB		3542	-1436
RTD		3664	-1558

8 5/8" 328/250sx; 5 1/2" 3664/250sx
 DV TOOL @ 1277/290sx
 DST (1) 3516-55 (ARB)/30-60-30-60,
 78' GSY OILY WTR M (25% OIL),
 204' SG & OCMW (5% OIL), SIP 766-
 757#, FP 9-70/70-122#
 DST (2) 3560-3600 (ARB)/30-60-50-60,
 200' GIP, 504' GSY OILY MW (25% OIL)
 1008' GSY OCW (5% OIL), 1410' SW,
 SIP 810-810#, FP 523-810/810-810#
 BHT 99°
 DST (3) 3603-34 (ARB)/30-60-30-60, 2950'
 SW, SIP 1097-1097#, FP 531-1097/
 1097-1097#, BHT 100°
 MICT - CO, PF (ARB) 4/3592-94, AC150G
 (15%), POP, REC LD, P 26 BO & 336 BW
 /24HRS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS