

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03442-00-00
Spot: W2NENE Sec/Twnshp/Rge: 25-11S-17W
660 feet from N Section Line, 990 feet from E Section Line
Lease Name: CALAHAN B Well #: 10
County: ELLIS Total Vertical Depth: 3410 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3385	0	125 SX
SURF	8.625	1035	0	300 SX

110.83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2008 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
08/22/2005 - Casing leak 2578' - 2761' - squeezed with 200 sxs.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2008 11:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3250' - pumped 12 sxs gel with 200# hulls - followed with 60 sxs 60/40 pozmix - 4% gel and 100# hulls - had circulation.
Pulled tubing to 1830' - pumped 130 sxs 60/40 pozmix - 4% gel with 300# hulls - circulated cement to surface.
Pulled all tubing - pumped 20 sxs 60/40 pozmix - 4% gel down backside.
S.I.P. 225#.
Hooked on to 5 1/2" - pumped 30 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3385	3410		OPEN HOLE

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 28 2008

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 4-10-08
INV. NO. 2008061525

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

MAR 27 2008


Contr. _____ ELLIS County

E 1900 Comm 10-8-41 Comp. 11-26-41 IP 3000 BOPD
ECHO

Tops	Depth	Datum
ANH	1085	75
ARB	3384	
TD	3410	

Casing
10" 1035
5" 3385

Perf 30/3385-92
2450' OIH/15hrs: A/7000



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

[Handwritten notes and scribbles]

[Handwritten notes]