

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-21,902 - 00-00 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171

ADDRESS 155 N. Market, Suite 1000, Wichita, KS. 67202 PHONE # (316) 269-7600

LEASE (FARM) Colahan WELL NO. #1 WELL LOCATION 330' FSL & 330' FWL COUNTY Rooks

SEC. 18 TWP. 9S RGE. 16 ~~KEY~~ (W) TOTAL DEPTH 3450' PLUG BACK TD N/A
4950' FEL

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 248' CEMENTED WITH 250 SACKS

CASING SIZE 4-1/2" SET AT 3449' CEMENTED WITH 125 SACKS

PERFORATED AT 3444-47', 3360-66', 3330-32', 3324-26', 3304-14', 3247-53', 3230-40', 3200-04', 3188093', 3179-86', 3166-70'

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 3130', dump 2 sxs sand followed

by 3 sxs cement. Pull ± 2000' of casing. Fill hole to bottom of surface casing with drilling

mud. Dump 10. sxs cement. Fill hole to 40' with mud. Dump 10 sxs cement. Cut off surface casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry W. Collins PHONE # (316) 886-5605

ADDRESS P.O. Box 125-B, R.R. #1, Medicine Lodge, KS. 67104

PLUGGING CONTRACTOR Clarke Corporation Oilfield Services LICENSE NO. 5105 6/87

ADDRESS 107 W. Fowler, Medicine Lodge, KS. 67104 PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Cory West
STATE CORPORATION COMMISSION (Operator or Agent)

DATE: October 3, 1986

10/6/86
OCT 6 1986

State of Kansas



15-163-21902-0000

JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE

JAN 7 '87

EXPIRES

October 7, 1986

WELL PLUGGING NOTICE

Colahan #1
330' FSL 4950' FEL
Sec. 18-9S-16W
Rooks County

TXO Production Corporation
155 N. Market, Ste. 1000
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "Jack McCord".

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #6 1014 Cody Hays, KS 67601 913-628-1200

five days prior to plugging the well (KAR-82-3-113).