

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-03623-00-02 (of this well) 6/86
January 13, 1948

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil & Gas Corporation OPERATORS LICENSE NO. 5447
ADDRESS 800 Sutton Place Bldg., 209 E. William
Wichita, Kansas 67202 PHONE # (316) 265-5624

LEASE (FARM) Dorr Unit WELL NO. 601 WELL LOCATION NE NE NW COUNTY Rooks
SEC. 20 TWP. 9S RGE. 16 ~~XXXX~~ (W) TOTAL DEPTH 3417' PLUG BACK TD 3382'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. E-9161
SURFACE CASING SIZE 8-5/8" SET AT 259' CEMENTED WITH 150 SACKS
CASING SIZE 4-1/2" SET AT 3417' CEMENTED WITH 150 SACKS
PERFORATED AT 3138-3399' (13 intervals perforated)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug #1 - PBTD to 3075'.
Plug #2 - 950-400', both inside and outside casing. Plug #3 - 310-210', both inside and
outside casing. Plug #4 - 50'-surface and 1" from 50' to surface in annulus. (over)

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Approximately July 15, 1985

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Dan Hoffman, Production Foreman PHONE # (913) 434-2350

ADDRESS Box 90, Plainville, Kansas 67663

PLUGGING CONTRACTOR Halliburton LICENSE NO. 7/1/85
ADDRESS 1100 E. 8th
Hays, Kansas 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Charles W. Horsman
Send Invoice To: Cities Service Oil & Gas Corporation (Operator or Agent)
Attention: Jacque Pierce Charles W. Horsman, Pet. Engineer
3545 N.W. 58th Street DATE: June 28, 1985
Oklahoma City, Oklahoma 73112

RECEIVED
STATE CORPORATION COMMISSION
JUL 01 1985
CONSERVATION DIVISION
Wichita, Kansas

④

Operator's Suggested Method of Plugging this Well.....continued.

NOTE: The Cheyenne and Dakota formations will be covered by a plug extending fifty (50') feet above and below their respective depths.



15-163-03623-00-02

JOHN CARLIN
MICHAEL LENNEN
ARGALEE WRIGHT
LITH R. HENLEY
EDITH A. McCONNELL
CHRISTIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

OCT 9 1985

July 9, 1985

EXPIRES

WELL PLUGGING NOTICE

Dorr Unit #601 (SWD)
NE NE NW
Sec. 20-9S-16W
Rooks County

Cities Service Oil & Gas Corporation
800 Sutton Place Bldg
209 E. William
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #6 1014 Cody Hays, KS 67601 913-628-1200

five days prior to plugging the well (KAR-82-3-113).