

15-163-03641-50-07

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API Number 7-11-56 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447 4/91

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000  
1980 FNL

LEASE/FARM Dorr Unit WELL NO. 903W WELL LOCATION 990 FEL COUNTY Rooks  
pwp

SEC. 21 TWP. 9S RGE. 16 (E) or (W) Total Depth 3470' PLUG BACK TD 3426'

CHECK ONE:

OIL WELL        GAS WELL        D & A        SWD OR INJ WELL X DOCKET NO. E-9161

SURFACE CASING SIZE 9-5/8" SET AT 246' CEMENTED WITH 170 SACKS

CASING SIZE 5-1/2" SET AT 3470' CEMENTED WITH 85 SACKS

PERFORATED AT 3184-3400' (11 sets)

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE 3282' FU at

PROPOSED METHOD OF PLUGGING Plugging proposal is attached for State approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: June 7, 1990

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. J. D. Hininger PHONE # (913) 674-2182

ADDRESS OXY USA INC., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Ostrom Well Service, Inc. LICENSE NO. 5680 4/90  
ADDRESS RR 1, Box 368, Plainville, Kansas 67663 PHONE # (913) 434-4538

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

MAY 8 1990

5/8/90

SIGNED: Philip Grings  
(Operator or Agent)

DATE: May 8, 1990

4



15-163-03641-00-07

MEMORANDUM  
OCCIDENTAL OIL AND GAS

Wichita, Kansas  
May 7, 1990

TO: Mr. M. D. Harrison

FROM: Mr. P. W. Pringle

SUBJECT: PLUG & ABANDON.....DORR UNIT #903W  
1980' FNL, ~~1990~~ FEL  
SEC 21-9S-16W <sup>PWP</sup>  
ROOKS COUNTY, KANSAS

WELL DATA

9-5/8" SURFACE @ 246' W/ 170 SX  
5-1/2" PRODUCTION @ 3470' W/ 85 SX  
PERFORATIONS: 3184-3400' (11 SETS)  
PBTD 3426'

- \* FILLUP MEASURED @ 3282'
- \* CASING LEAKS 2088-2181', 757-788', 492-523'

SHALLOW FORMATIONS

DAKOTA 514'  
CHEYENNE 1000'  
ANHYDRITE 1300'

1. Prior to plugging, obtain approval of project from the KCC District Office #4, Hays, Kansas (913) 628-1200.
2. Run in well with 2" work string to ±3200' and spot to surface the following: 50 sx Class "A" cement followed w/ approximately 300 sx 65/35 cement w/ 6% gel (use hulls as needed). Lay down work string. If circulation was not established, tie onto the surface casing and pump 100 sx cement down annulus. Have approximately 800# hulls at location.
3. Let cement set 48 hours, check TOC and cap well.

RECEIVED  
STATE ~~PROTECTION~~ COMMISSION

PWP/cd

MAY 8 1990

CONSERVATION DIVISION  
Wichita, Kansas