

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-163-20405-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1971

CONSERVATION DIVISION  
Wichita, Kansas

12-10-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of L. J. Dreiling has this

date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources

Complete Address: 1000 century Plaza Wichita, Ks.

Lease Name: Andresom Well No. 1

Location: NE NW SE Sec. 29 Twp. 10 Rge. (E)(W) 18

County: Rooks Total Depth 3285' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 575' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Mussey  
Conservation Division Agent