

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1967

08-14-1967

CONSERVATION DIVISION
WICHITA, KANSAS

15-163-20049-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dobbs of Edmiston Drl. has this

date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bldg. Wichita, Kansas

Lease Name: Sheppard Shepard ^{Ac} Well No. 1

Location: NW NE NE Sec. 25 Twp. 10 Rge. 18 (E)(W) X

County Rooks Total Depth 3690 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
90 sc cement thru drill pipe. Heavy mud to 200' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent