

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-163-20195-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1969
CONSERVATION DIVISION
Wichita, Kansas
04-07-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg. Co.

Complete Address: 801 Union Center Wichita, Ks.

Lease Name: Schmidt Well No. X 2 AWH KCC

Location: SW NW SE Sec. 25 Twp. 10 Rge. (E)(W) 18

County: Rooks Total Depth 3605 Oil Well

Gas Well Input Well SWD Well D & AXX Lost Hole

Mr. Cook was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 650' and displace

70 sk cmt thru drill pipe. Heavy mud to 249' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk hnt to base of cellar. Plug rat hole with

2 sk cmt.

Very truly yours,

Leo J. Messing
Conservation Division Agent