

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15831-00-01
Spot: SESENE Sec/Twnshp/Rge: 36-17S-11W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: BRADLEY Well #: 1
County: BARTON Total Vertical Depth: 3245 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	3199		50 SX CMT.
PROD 7		3236	1420	w/unknown sxs cmt
SURF	10.75	144	0	w/unknown sxs cmt
T1	2.875	3225		

\$ 105,460

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2008 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 4% gel - 21 sxs gel - 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2008 11:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied to casing - pumped 40 sxs cement with 100# hulls.
Pumped 21 sxs gel with 400# hulls.
Pumped 150 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 750#.

Perfs:

INVOICED
DATE 4-3-08
INV. NO. 2008061457

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 18 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #33568.

Plugged through: CSG

District: 04

FD

Signed Bruce Rodie
(TECHNICIAN)

PKT

CARMEN SCHMITT
GREAT BEND KS 67530

36-17S-11W
SE SE NE

#1 BRADLEY OWWO

site 2-1/2 E OF CLARLIN KS
contr: DS & W WELL SVCG
prod: NONE

op: BARTON
field: BLOOMER

API 15-009-15831 - 00-0

fr date 05/01/2006 spd date 04/28/2006 drg comp 05/19/2006 card issued 08/21/2006 last revised 08/21/2006

ELV: 1805 KB, 1803 GL SMP
tops.....depth/datum
ARB.....3236 -1431
RTD OLD.....3242 -1437
LTD.....3245 -1440

IP status
OIL, ARB 3199-3245, 06/15/2006
OLD INFO: OPERATOR WAS SKELLY OIL CO, 7
BLOOMER, J. B., SPD 01/13/1937, 02/04/1937 10-3/4" 144 (ALT
2), 7" 3236, OIL/GAS, P 2,854 BOPD, NW & 10 MCFGPD, ARB
3236-3242, 07/13/1937 (CARD ISSUED 09/01/1947)
CONTR: UNKNOWN
COMMENT: WAS TEMP API IOG-6577
CORE (1) 3241-3242 (ARB), CUT 1" - DETAILS NA
NO TESTS
MICT - CO, (ARB OH), GSO, NAT, AC 1000 GAL, GSO, POP,
IFP 2854 BOPD, NW & 10 MCFGPD, GOR 3.5:1, 7/13/1937
(WELL P & A 9/1/1966)
NEW INFO: FR 05/01/2006, RE-ENTERED 04/28/2006 WSH
DWN, LOGGED DC 05/19/2006 CSG: PROD CSG ALREADY
IN HOLE, RAN 5-1/2" LINER TO 3199
(over)

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

COMMENT: KCC API 15-009-15831-0001
TRGT ZN: ARB (OIL), PTD 3250 (ARB), MICT - CO, (ARB OH), SWB DWN, SO, POP, OIL
(POTENTIAL NOT RPTD), 6/15/2006 - TIGHT HOLE - NO OTHER INFO AVAILABLE - TEMP COMP
7/21/2006