

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20208-00-00
Spot: SWNENW Sec/Twnshp/Rge: 25-2S-19W
990 feet from N Section Line, 1650 feet from W Section Line
Lease Name: WEINMAN B Well #: 1
County: PHILLIPS Total Vertical Depth: 3502 feet

Operator License No.: 3077
Op Name: JOHNSON OIL, A GENERAL PARTNERS
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3516	0	w/150 sxs cmt
SURF	8.625	210	0	w/165 sxs cmt

\$ 113.82

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2008 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL, A GENERAL PARTN Phone: (785) 543-6171

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 800# hulls.
Perforated 1175' and 1750'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2008 2:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2016' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls. Had circulation.
Pulled tubing to 1000' - pumped 70 sxs 60/40 pozmix - 4% gel with 200# hulls.
Cement circulated to surface.
Pulled all tubing - pumped 20 sxs 60/40 pozmix - 4% gel down 4 1/2" casing. S.I.P. 400#.
Pumped 235 sxs 60/40 pozmix - 4% gel down backside. S.I.P. 50#.

Perfs:

INVOICED
DATE 4-3-08
INV. NO. 2008061463

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 18 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #30303.

Plugged through: TBG

District: 04

PD

Signed _____

Pat Bedore

(TECHNICIAN)

MAR 17 2008

PK

PETROLEUM MANAGEMENT, INC.

#1 WEINMAN 'B'

25-2-19
SW NE NW

400 N. WOODLAWN WICHITA, KS.

CONTR. PEO TIGER DRUG. CO.

CTY. PHILLIPS

GEOLOGIST BILL PETERSEN

FIELD DAYTON EXT

E 2170 2A CM 12/2/75 ^{CARD} ISSUED 2/19/76 IP P 30 BOPD + 50 BWPD
API 15-147-21,208 LKC 3362-3408 O.A.

SMP	TOPS	DEPTH	DATUM
ANK Base	1740	1740	+430
TOP	3076		-906
LKC	3324		-1154
RTD	3550		-1380

8 5/8" 210/165sx, 4 1/2" 3516/150sx
MICT - PF 3362-66, 3380-24, 3398-95,
3404-3409, A 3000, SWB 10 80/1HR, 20F

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS