

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20218-00-00
Spot: SWSESW Sec/Twnshp/Rge: 29-15S-41W
349 feet from S Section Line, 3928 feet from E Section Line
Lease Name: KUDER Well #: 1-29
County: WALLACE Total Vertical Depth: 5261 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2760	0	675 SX CMT.
SURF	8.625	371	0	225 SX CMT.

\$ 170.98

Well Type: SWD UIC Docket No: D26920.0 Date/Time to Plug: 03/21/2008 8:30 AM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: SHANE PELTON Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel.
CIBP 2560'. MIT 300# 12/28/2005.
Cedar Hills 2574' - 2664'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2008 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2560'. Tagged CIBP.
Pulled to 2540'. Allied pumped 125 sxs 60/40 pozmix - 4%gel.
Pulled tubing to 1330'. Allied pumped 110 sxs cwc.
PTOH. Topped off with 25 sxs cement. Casing full.
Hooked up to backside. Allied pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
2610	2650		

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 25 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 4-3-08
INV. NO. 2008061466

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN) cm