

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22033-00-00
Spot: NESWSW Sec/Twnshp/Rge: 6-20S-10W
993 feet from S Section Line, 4051 feet from E Section Line
Lease Name: SCHARTZ LEWIS Well #: 2
County: RICE Total Vertical Depth: 3360 feet

Operator License No.: 33315
Op Name: MAR-LOU OIL CO., LLC
Address: PO BOX 218
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3359	1100	
SURF	8.625	219		

\$ 109.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2008 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2008 11:00 AM KCC Agent: TROY RUSSELL

Actual Plugging Report:

CEMENT BOND LOG INDICATED APPROXIMATE CEMENT TOP AT 1100'. CUT CASING @ 1100' AND PUMPED 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 900' AND PUMP 35 SXS CEMENT WITH 50#'S COTTON HULLS. PULL CASING TO 270' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT OF HOLE AND TOP OFF WITH CEMENT.

Perfs:

INVOICED
DATE 4-3-08
INV. NO. 2008061468

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT #1872

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

PLT