

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21077-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 35-17S-12W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SCHNEWEIS Well #: 1
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: 125 N MARKET STE 1230
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3361	0	200 SX
SURF	8.625	273	0	175 SX

\$ 109.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2008 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: NOVY OIL & GAS, INC. Phone: (316) 265-4651

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2008 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Reida pump stuck in pipe at 2124'. Perfed tubing at 2100'.
Tied to tubing - pumped 330 sxs cement. Let set overnight.
Tagged cement at 974' in tubing - perfed at 962' - could not pump in tubing.
Pulled up 400' - perfed - could not pump - ran one foot pipe tubing.
Circulated cement to top in tubing and casing.

INVOICED
DATE 4-3-08
INV. NO. 2008061472

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 18 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #33421.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

Form CP-2/3

MAR 17 2008

PCT

C OIL, INC.
 606 PETROLEUM BLDG.
 WICHITA, KS. #1 SCHNEWEIS 35-17-12W
 CONTR RED TIGER DRILLING CO. CTY BARTON SE NW NE
 GEOL CARL TODD FIELD MC (SNOW WHITE DISC)
 E 1843 KB CM 9/14/76 CARD ISSUED 11/11/76 IP P 62 BOPD + 5% W
 ARB 3361-70

API 15-009-21,077

LOG	TOPS	DEPTH	DATUM
Awk		706	
TOP		2552	- 819
HEEB		2955	-1112
TOR		2975	-1132
BR LM		3058	-1215
LANS		3074	-1231
ARB		3350	-1507
LTD		3368	-1525
DDTD		3370	-1527

8-5/8" 273/175sx, 5 1/2" 3361/200sx
 DST (1) 2902-09/45-45-30-50, 5' M, SIP
 1012-931# FP 20-20# 20-20#
 DST (2) 3059-3129/45-45-60-45, 25' GIP
 45' SO&GCM, SIP 283-202# FP 40-60#
 50-60#
 DST (3) 3195-3250/60-45-15-15, 20' OCM,
 SIP 121-60# FP 30-40# 40-40#
 DST (4) 3340-53/30-30-20-20, 10' OCM +
 SO, SIP 404-101# FP 10-20# 20-20#
 DST (5) 3350-64/45-45-90-45, 20' CO, 60'
 MO, 60' VHOCM, SIP 1113-1093# FP 20-
 40# 40-81#
 MICT - CO TO, TEST 20 GOPH, DD 3370, SWB
 52 80/5 HRS, SO/15 HRS, FU 3100' OIL +
 TR WTR, POP.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS