

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22040-00-00
Spot: SENWSW Sec/Twnshp/Rge: 31-18S-7W
1632 feet from S Section Line, 4412 feet from E Section Line
Lease Name: BOLTON Well #: 12
County: RICE Total Vertical Depth: 3379 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3379		200 SX CMT.
SURF	8.625	228		160 SX CMT <u>\$109.82</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2008 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Propoal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 03/14/2008 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND TO 3200' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1050', 700' AND 278'. RUN TUBING TO 1050' AND UMP 35 SX'S CEMENT. PULL TUBING TO 700' AND PUMP 35 SXS CEMENT. PULL TUBING TO 278' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT OF HOLE AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3258	3262		
3250	3254		

INVOICED
DATE 4-3-08
INV. NO. 2008061475

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 45 GEL. COPELAND TICKET C-33570. LOG TECH PERF TICKET #5208.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

[Handwritten initials]