

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20731-00-00
Spot: W2SW Sec/Twnshp/Rge: 33-10S-33W
1000 feet from S Section Line, 380 feet from W Section Line
Lease Name: AHRENS Well #: M 1
County: THOMAS Total Vertical Depth: 4765 feet

Operator License No.: 3988
Op Name: SLAWSON EXPLORATION COMPANY, I
Address: 204 N ROBINSON AVE STE 2300
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	375		

\$ 154.86

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/04/2008 2:00 PM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: WES Company: H2 DRILLING LLC Phone: (620) 272-3988

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 03/04/2008 4:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2700' w/25 sxs.
2nd. Plug at 1825' w/100 sxs.
3rd. Plug at 425' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 4-3-08
INV. NO. 2008061479

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

District: 04

Signed [Signature]
(TECHNICIAN)

MAR 21 2008

[Handwritten initials]