

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-077-21613-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 25-33S-6W
990 feet from S Section Line, 1320 feet from E Section Line
Lease Name: F AND R HOOPS Well #: V1-25
County: HARPER Total Vertical Depth 4575 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	223	0	

Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

148.69 ~~148.69~~

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2008 10:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: GREG DAVIDSON Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: Fill hole with heavy mud & spot cement through drill pipe. Spot 35 sxs. cement @ 1,000', 35 sxs. cement @ 650', 35 sxs. cement @ 270', 25 sxs. cement @ 60', 15 sxs. cement in rat hole, & 10 sxs. cement in mouse hole.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 03/09/2008 12:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Filled hole with heavy mud & spotted cement through drill pipe. Spotted 35 sxs. cement @ 1,000', 35 sxs. cement @ 650', 35 sxs. cement @ 270', 25 sxs. cement @ 60', 15 sxs. cement in rat hole, & 10 sxs. cement in mouse hole.

Perfs:

INVOICED
DATE 4-3-08
INV. NO. 2008061481

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 20 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, LLC. INVOICE #31047.

Plugged through: DP

District: 02

Signed Michael R Wilson
(TECHNICIAN)

PKT