

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20382-00-00
Spot: NW Sec/Twnshp/Rge: 4-31S-40W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: WILLIAMS BROS Well #: 1-4
County: MORTON Total Vertical Depth: 2376 feet

Operator License No.: 5156
Op Name: WHITE, EDGAR W.
Address: 701 VILYMACA ST PO BOX 450
ELKHART, KS 67950

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2359	870	
SURF	8.625	611		

Handwritten: \$ 77.22

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/18/2008 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PLUG AT 1660' WITH 50 SX CMT OR 25 SX CMT IN 4 1/2" IF DON'T GET ENOUGH STRETCH. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2008 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:
PUMP 200# HULLS & 50 SX CMT AT 2260'. 1ST PLUG AT 640' WITH 50 SX CMT. 2ND PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2325	2332		
2280	2297		
2260	2270		

INVOICED
DATE 4-3-08
INV. NO. 2008061483

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 24 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.
Plugged through: CSG

District: 01 Signed Jack L Maclosky
(TECHNICIAN)

RECEIVED
MAR 19 2008
KCC Dodge City

Form CP-2/3
Handwritten initials: PLS, [Signature]