

RECEIVED  
KANSAS CORPORATION COMMISSION

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
September 2003

MAR 04 2008

WELL PLUGGING APPLICATION

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

Please TYPE Form and File ONE Copy

CONSERVATION DIVISION

WICHITA, KS

API # 15-095-19047-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Spud 07/11/1953

Well Operator: Woolsey Operating Company LLC KCC License #: 33168

Address: 125 N. Market, Suite 1000 (Owner / Company Name) City: Wichita (Operator's)

State: Kansas Zip Code: 67202 Contact Phone: ( 316 ) 267 - 4379

Lease: RITCHEY Well #: 1 SWD Sec. 2 Twp. 28 S. R. 5  East  West

- SW - SW - SE Spot Location / QQQQ County: KINGMAN

330 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # 3,656  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" x 28# Set at: 181' Cemented with: 125 Sacks

Production Casing Size: 5 1/2" x 14# Set at: 4396' Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: Arbuckle 4335'-39' & 4352'-57'. Open hole 4396'-4566'

Miss 3772'-78' (packer set at 3755' & squeezed)

Elevation: 1405' ( G.L. /  K.B.) T.D.: 4556' PBTD: 4566' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): CIBP at 4270' w/ 2 sx, 35 sx at 900', 35 sx at 450',  
then circ cmt from 250' to surface (per Steve van Gieson)

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Drilled in 1953

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Carl W. Durr, Field Manager

Phone: ( 620 ) 886 - 5606 ext. 27

Address: 1966 SE Rodeo Drive City / State: Medicine Lodge, KS 67104

Plugging Contractor: Pratt Well Service KCC License #: 5893

Address: P.O. Box 847, Pratt, KS 67124 Phone: ( 620 ) 672 - 2531

Proposed Date and Hour of Plugging (if known?): upon approval

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 03/03/2008 Authorized Operator / Agent: \_\_\_\_\_

Dean Pattison, Operations Manager (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# KANSAS

## CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

WOOLSEY OPERATING COMPANY, LLC  
125 N MARKET STE 1000  
WICHITA, KS 67202-1729

March 18, 2008

Re: RITCHEY #1  
API 15-095-19047-00-00  
2-28S-5W, 330 FSL 2310 FEL  
KINGMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after September 14, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

*Steve Bond*

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000