

**Give All Information Completely  
Take Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas**

Butler

County. Sec. 31 Twp 27S Rge 3 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CNL NW SE

Lease Owner H. V. Elwell & E. B. Shawver

Lease Name B. I. Stephens Well No. 1

Office Address 310 Petroleum Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed..... July 11..... 1950

Application for plugging filed..... July 11 1950

Application for plugging approved..... July 11 1950

Plugging commenced ..... July 12 ..... 1950

Plugging completed..... July 13 1950

Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production.....19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well. A. L. Loman

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 2009 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Dumped 3 sax of cement @ 2009'; filled with mud to 150'; set wooden plug at 150', and dumped in 10 sax of cement. Filled with mud to top of surface pipe, put in 5 sax of cement. Capped same.

7/18/50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to E. B. Shawver  
Address 310 Petroleum Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

..... S. D. Batz ..... (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

310 Petroleum Bldg., Wichita, Kansas


.....  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 1950

My commission expires Dec. 16, 1953

22-7377-s

4-49-10M



15-015-19582-00-00

L O G

B. L. STEPHENS NO. 1, CNL NW SE Sec. 31-27S-3E, Butler County, Kans.

Owners: H. V. Elwell & E.B. Shawver  
Contractor: E. B. Shawver

Drilling commenced: Cable  
tools May 13, 1950; rotary  
tools, July 3, 1950  
Drilling completed: July 11, 1950

8-5/8" 81'

Elevation: 1288'

surface (cable tools)	22
shale	26
lime	27
water sand	30
lime & shale B.	60
shale	63
lime	68
shale	70
lime	82
shale	92
lime	130
shale	136
red rock	138
lime	142
shale pink	158
lime	320
lime & shale break	330
red rock	340
lime	355
sand & shale	366
shale	371
lime	416
shale	418
red rock	420
lime (rotary)	480
shale & shells	1770
lime	1795
shale & shells	1987
shale	1997
red rock	1999
Stalnaker sand-water	2009 T.D.

D & A

