


WELL PLUGGING RECORD

Give All Information Completely
Map Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County, Sec. 31 Twp. 27 Rge. 3 (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines SW SW SE
Lease Owner L. C. Smitherman Oil Producer
Lease Name Burke Well No. 1
Office Address Box 627 - Augusta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-13 19 56
Application for plugging filed 2-13 19 56
Application for plugging approved 2-13 19 56
Plugging commenced 2-13 19 56
Plugging completed 2-13 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence Matthews
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3168 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale & Sand	water	0	50			
Lime		50	101	8 5/8	101	None
Lime (Kansas City)		2358	2538			
Mississippi Lime		2830	2910			
Simpson Sand		3129	3168			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 240' and set plug. 12 sacks of cement on top of plug. Mud to 20' with 5 sacks of cement to 2' below surface level. Steel plate welded on top.

RECEIVED
STATE OF KANSAS
2/25/56
FEB 25 1956

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. C. Smitherman Drilling Company
Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler ss.
Joe W. Cain (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain
Box 627 - Augusta, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of February, 1956

Ruth H. Carter
Notary Public.

My commission expires October 23, 1958.

PLUGGING
FILE SEC 31 T 27 R 3E
BOOK PAGE 40 LINE 12

15-015-00256-00-00

BURKE #1

Company	- L. C. Smitherman Oil Producer	Location:	SW SW SE, Sec. 31-27-3E, Butler
Contractor	- L. C. Smitherman Drlg. Co.		County, Kansas
		Elevation:	
Commenced	- 2- 4-56	Casing:	8 5/8" - 101' cemented W/100
Completed	- 2-13-56		Sacks cement.
Initial Prod.	- D & A		
Total Depth	- 3168'		

FIGURES INDICATE BOTTOMS OF FORMATIONS:

Depth	Formation
90 - 365	Shale & Lime
365 - 561	Shale & Lime Strks.
561 - 890	Shale & Shells
890 - 1040	Sandy Shale & Lime
1040 - 1165	Sandy Shale W/Lime Strks.
1165 - 1456	Shale & Lime Strks.
1456 - 1672	Shale & Lime
1672 - 1804	Sandy Lime & Shale
1804 - 1870	Shale & Lime
1870 - 1920	Sandy Shale W/Lime
1920 - 1957	Shale & Lime
1957 - 2071	Shale & Lime W/Sand Strks.
2071 - 2110	Shale & Lime
2110 - 2360	Shale
2360 - 2369	Shale & Lime
2369 - 2448	Lime (K.C.)
2448 - 2490	Lime W/Sandy Shale Breaks
2490 - 2854	Lime & Shale
2854 - 2910	Lime & Chert
2910 - 2939	Chert & Lime
2939 - 2984	Lime & Chert
2984 - 3138	Lime & Shale
3138 - 3168	Coreing - Simpson Sand
3168 - R. T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Burke #1, located in the SW SW SE of Section 31-27-3E, Butler County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

George R. Shert

Subscribed and sworn to before me this 24th day of February, 1956.

Ruth A. Carter

Notary Public

My commission expires October 23, 1958.

PLUGGING
 FILE SEC 31 T 27 R 3E
 BOOK PAGE 40 LINE 12