

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-015-19796-00-00

9.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Butler

County. Sec. 28 Twp. 27 Rge. 3 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW-NW-NE

Lease Owner Shawver - Armour Inc.

Lease Name Crescent Heights Well No. 1

Office Address 817 Central Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 8-19-61 19 61

Application for plugging filed 8-21- 19 61

Application for plugging approved 8-17- 19 61


Plugging commenced 8-19 19 61

Plugging completed 8-19 19 61

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Lee Guthrie

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3175 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole back to 2400', mixed and run 3 sacks cement. Pulled casing, mudded hole to 180' set 10' rock bridge mixed and run 15 sack cement with dump bailer, mud to 40' set 10' rock bridge of 10 sack cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
8/23/61
AUG 23 1961

CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Mr. Hershel Shawver (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren W. Starnes

(Address) _____

SUBSCRIBED AND SWORN TO before me this 22 day of August, 19 61
Shirley D. Miller
Notary Public.



15-015-19796-00-00

9

DRILLER'S LOG

FARM NAME: Crescent Heights # 1 LOCATION: Appr. NW NW NE
 CONTRACTOR: SHAWVER ARMOUR, INC. Sec. 28-27S-3E
 BUTLER COUNTY, KANSAS
 OWNER: SHAWVER ARMOUR, INC. ELEVATION: 1330 K B
 COMMENCED: July 1, 1961 COMPLETED: July 10, 1961
 CASING RECORD: 195' 8 5/8" w/175 sacks cement 2% cc

FORMATION:*

TOPS:

Lime & Shale 645
 Shale -Lime & Shells 1135
 Shale & Lime 1800
 Lime & Shale 1937
 Lansing 2035
 Lansing-Shale 2276
 Shale & Lime 2327
 Kansas City Lime 2351
 Lime 2357
 Shale & Lime 2448
 Kansas City Lime 2520
 Shale 2530
 Shale & Lime 2788
 Mississippian Lime 2850
 Lime 2917
 Lime & Shale 3009
 Lime 3015
 Shale-Lime 3075
 Sand 3080
 Simpson 3146
 Rotary Total Depth 3175

Lansing 1937
 Kansas City 2327
 Base Kansas City 2519
 Mississippian 2788
 Kinderhook 3004
 Simpson 3069
 Arbuckle 3146

STATE CORPORATION COMMISSION
 AUG 13 1961
 CORRELATION DIVISION
 TOPEKA, KANSAS

STATE OF KANSAS)
) ss
 SEDGWICK COUNTY)

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY: James M. Armour
 James M. Armour

Subscribed and sworn to before me this 11th day of July, 1961.

My commission expires Dec. 29th, 1963

Marjorie Hall
 Marjorie Hall, Notary Public

