

LEASE NAME Mollett

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 7

1550 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 28 RGE. 2 (E) or (W)

COUNTY Sedgwich

LEASE OPERATOR Prairie State Petro.

ADDRESS P.O. Box 305, Leon

PHONE# (316) 745-3754 OPERATORS LICENSE NO. 03095

Character of Well Good

Date Well Completed _____

Plugging Commenced 9-28-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-1-94

The plugging proposal was approved on 9-12-94 (date)

by -Mike Wilson - (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	217	None
				5 1/2	3335	2100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Sanded bottom to 3155, dumped 5sx cement at 3155 with bailer, cut and pulled casing to 270, circulated to surface, pulled casing, top off, cement to surface

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Clarke Corporation

License _____

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Prairie State Petro.

STATE OF Kansas COUNTY OF Barber, ss.


Jeff Sletto

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Jeff Sletto


(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 14 day of October, 1994

[Signature]
Notary Public

My Commission Expires: 6-21-95



API#15-173-20554

9-28-22

L. E. CARTER
K. G. S. LIBRARY
 Petroleum Geologist

Office Phone
 (516) 267-2489

Home Phone
 Wichita, Kansas 67201

Home Phone
 (516) 700-7011

GEOLOGIST'S REPORT

DRILLING TIME AND SAMPLE LOG

COMPANY Wiley R. Ash, Inc.
 LEASE Mollet - Well No. 7
 FIELD Gehring - Rick North
 LOCATION 130' south of St. Peter
 SEC. 9 TWSP 28 South RNG. 4
 COUNTY Sedwick STATE Kansas

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 12 1994
CONSERVATION DIVISION
WICHITA, KS

ELEVATIONS
 K. B. 1355'
 D. F. 1355'
 G. L. 1350'
 Measurements Are All
 From 1355' K.B.

CONTRACTOR Raymond Drilling
 SPUD 1:50 P.M. 3/9/83 COMP Had 5 1/4" casings
 RTD 2:30 3/9 LTD in hole 3550'
 MUD UP 2551' 2/Gal TYPE MUD Water Gel

CASING
 SURFACE 2 1/2" 217'
 PRODUCTION 5 1/2" 3535'

ELECTRICAL SURVEY
 Corbhatt: Density Log
 & Radiation Count Log

FORMATION TOPS & STRUCTURAL POSITION

FORMATION	DRILLING TIME	ELECTRIC LOG TOP	SUB SEA DATUM	STRUCTURAL POSITION		
				A	B	
Heebner Sh Mbr.	1912'	1904'	-549	-559	-549	-556
Douglas Sh Group	1945'	1957'	-582	-585	-584	-586
Ireland Sd Mbr.	1996'	1988'	-655	-628	-652	-646
Kansas City Ln Fm	2498'	2492'	-1137	-1140	-1138	-1144
Base Kansas City	2698'	2692'	-1377	-1340	-1342	-1348
Marathon Ln Fm	2774'	2769'	-1414	-1418	-1411	-1419
Cherokee Sh Group	2923'	2925'	-1508	-1570	-1571	-1584
Top Mississippian	2951'	2946'	-1591	-1596	-1599	-1607
Base Sedalia Ln	3194'	3139'	-1784	-1785	-1791	-1801
Chouteau Ln Fm	3175'	3169'	-1814	-1816	-1824	-1831
Kinderhookian Sh Fm	3195'	3191'	-1850	-1857	-1845	-1855
Simpson Group Sd	3240'	3245'	-1890	-1895	-1901	-1909
St. Peter Sd Mbr	3290'	3286'	-1951	-1954	-1959	-1952
Arbucke Dolm Fm	3555 1/2'	3551 3/4'	-1966 3/4'	-1978	-1981	-1999

REFERENCE WELLS FOR COMPARISONS

Electric log subsea tops used for structural comparisons.

A	Wiley Ash - Mollet #2, SE - NE - SE	Sec. 9 - T28S - R2E	
B	" " " #5, NE - SE - SE	" " "	
	" " " #1, SW - NE - SE	" " "	

I hereby certify that all oil zones of interest