

API NUMBER 15-173-20,519-00-00

LEASE NAME Mollett

WELL NUMBER 6

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 28 SRGE. 2 (E) or XX

COUNTY Sedgewich

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-3-94

Plugging Completed 10-5-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Prairie State Petro.

ADDRESS Box 305, Leon

PHONE# (316) 745-3754 OPERATORS LICENSE NO. 03095

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-12-94 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	212	None
				5 1/2	3310	1600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Sanded bottom to 2520, dumped 5sx cement at 2520 with bailer, cut and pulled casing to 265 feet, circulated cement to surface, pulled casing, topped off with cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Prairie State Petro.

STATE OF Kansas COUNTY OF Barber, ss.


Jeff Sletto (Employee of Operator) (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well and the statements, and matters herein contained and the log of the above-described well as filed with the Commission and the same are true and correct, so help me God.


(Signature) Jeff Sletto

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 14 day of October, 19 94



My Commission Expires: 6-21-95  
Caren J. Winchell  
Notary Public



# K. G. S. LIBRARY <sup>Moore</sup> GEOLOGIST

9-28-22

1007 BITTING BLDG.  
WICHITA, KANSAS 67202 API #15-173-20519 Ph 265-7541

## GEOLOGIST'S REPORT DRILLING TIME AND SAMPLE LOG

COMPANY WILEY R. ASH, SR.  
LEASE #6 Mallett  
FIELD \_\_\_\_\_  
LOCATION SE SE SE  
SEC. 9 TWSP. 28 S RNG. 2 E  
COUNTY Sedgewick STATE Ks.

ELEVATIONS

K.B. 1366  
D.F. \_\_\_\_\_  
G.L. \_\_\_\_\_  
Measurements Are Al.  
From KB.

CONTRACTOR Reynolds #3.  
SPUD 9-7-82 COMP 9-16-82  
RTD 3312 LTD 3308'  
MUD UP 2350' TYPE MUD Chemical.

CASING

SURFACE 6 7/8" @ 200'  
PRODUCTION \_\_\_\_\_  
  
ELECTRICAL SURVEYS  
GR-N-G-Col.

SAMPLES SAVED FROM 1900' TO TD.  
DRILLING TIME KEPT FROM 2100' TO TD.  
SAMPLES EXAMINED FROM 2100' TO TD.  
GEOLOGICAL SUPERVISION FROM 2350' TO TD.  
GEOLOGIST ON WELL DON F. MOORE

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
SEP 12 1994  
CONSERVATION DIVISION  
WICHITA, KS

FORMATION TOPS	LOG	SAMPLES
<u>Lansing</u>	<u>2220(-854)</u>	
<u>Kansas City</u>	<u>2502(-1136)</u>	
<u>Miss.</u>	<u>2958(-1592)</u>	
<u>Kindredhook</u>	<u>3168(-1802)</u>	
<u>Simpson</u>	<u>3230(-1869)</u>	
<u>Sp. Sd.</u>	<u>3279(-1913)</u>	
<u>TD.</u>	<u>3308(-1942)</u>	<u>3312(-1946)</u>


REMOVED