

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

County. Sec. 9 Twp. 28 Rge. 2E E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines

SW NE SE

Lease Owner Wiley R. Ash, Sr.

Lease Name Mollett Well No. 1

Office Address R.R. #1 Box 114, Rose Hill, KS 67133

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry

Date Well completed 2/8 1982

Application for plugging filed 2/8 1982

Application for plugging approved 2/8 1982

Plugging commenced 2/8 1982

Plugging completed 2/8 1982

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation Depth to top Bottom Total Depth of Well 3360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	208'	8 5/8	208'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up to 210' Plug 30 Sacks Cement
Mud up to 60' Plug 20 Sacks Cement
5 Sacks Cement In Rathole

RECEIVED
STATE CORPORATION COMMISSION
2-16-82
FEB 16 1982

CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EDCO Drilling Company, Inc.

STATE OF Kansas COUNTY OF Butler, ss.
(employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) A.C. Teutgen
Box 645, El Dorado, Kansas 67042
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 1982

DARLENE L. BRUNER
Statewide Notary Public
Butler County, Kansas
My Appt. Exp. 8-27-82

Darlene L. Bruner
Notary Public.

My commission expires



EDCO Drilling Company, Inc.

124 WEST LOCUST — P.O. BOX 645 — EL DORADO, KANSAS 67042

February 10, 1982

To: Wiley R. Ash, Sr.
R.R. #1 P.O. Box 114
Rose Hill, Kansas 67133

Lease: Mollet #1

Location: Sec. 9, Twp. 28S, Rge. 2E
Sedgwick County

Drilling Dates: February 1 thru February 8, 1982

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1982

CONSERVATION DIVISION
Wichita, Kansas

Drilling Log

Surface T.D. 213'
Surface Set 208' of 8 5/8" Surface Casing
Cemented by United 150 sacks cement 3% c.c.

150 - 205'	Cement
205 - 562'	Shale
562 - 870'	Shale mixed w/Lime Streaks
870 - 1410'	Shale w/Lime Streaks
1410 - 1690'	Shale w/Lime Streaks
1690 - 1935'	Shale w/Lime Streaks
1935 - 2205'	Shale w/Lime Streaks
2205 - 2230'	Lansing
2230 - 2475'	Lansing
2475 - 2498'	Lansing
2498 - 2654'	Kansas City Lime
2654 - 2700'	Kansas City
2700 - 2811'	Down Hole Shale w/Lime Breaks
2811 - 2962'	Shale w/Lime Streaks
2962 - 2964'	Shale w/Lime Streaks
2964 - 3190'	Mississippi
3190 - 3234'	Kinderhook
3234 - 3264'	Simpson
3264 - 3330'	Simpson
3330 - 3344'	Arbuckle
3360'	T.D.