

15-173-00434-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick

County. Sec. 9 Twp. 28S Rge. 2 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/4 NE/4 SE/4

Lease Owner John P. Gaty

Lease Name Thomas Well No. 2

Office Address 11 Cypress Dr., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 3/19 1954

Application for plugging filed 1/11 1955

Application for plugging approved 1/12 1955


Plugging commenced 1/13 1955

Plugging completed 1/17 1955

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3349 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3349' to 3240' & 6 sacks cement
Mud from 3340' to 170'
20' rock bridge with 20 sacks cement at 170'
Mud to surface
Capped with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John P. Gaty
Address 11 Cypress Dr., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Earl Wentworth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl Wentworth

734 Pippin Court, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of January 1955

My commission expires December 12, 1955

Arnold Dowd
Notary Public.

PLUGGING
FILE SEC 9 T 28 R 2 E
BOOK PAGE 90 LINE 23

JAN 20 1955
CONSERVATION DIVISION
WICHITA, KANSAS

#2
WELL LOG - Thomas #1

OPERATOR: Mr. J. P. Gaty
 11 Cypress Drive
 Forrest Hills
 Wichita, Kansas

LOCATION: NW NE SE
 Section 9-28S-2E
 Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
 Drawer 712
 El Dorado, Kansas

PRODUCTION: _____

Farm: Thomas Well #2

Date Commenced: February 8, 1954
 Date Completed: February 18, 1954

Elevation: 1350' DF

Total Depth: 3257' - Rotary

ROTARY T.D. (CORRECTED) 3256

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>CABLE TOOL LOG</u>
45	75	Cement	
75	85	Lime	
85	110	Lime & Shells	3256-3287 Sand
110	130	Shale & Lime	3287-3301 Sand & soft, gray-green shale.
130	300	Lime w/shale brks.	
300	310	Red Bed	3301-3309 Sand
310	565	Lime & Shale	3309-3319 Sandy dark gray shale
565	730	Shale & Lime strks.	3319-3347 $\frac{1}{2}$ Sand & green shale
730	800	Lime & Shale	3347 $\frac{1}{2}$ -3349 Arbuckle dolomite.
800	1080	Shale & Lime shells	
1080	1290	Shale & Lime strks.	
1290	1535	Shale & Lime	<u>FLUID RECORD BELOW PIPE</u>
1535	1665	Lime & Shale	3256-3257 2 BU/d, 25 BW/D
1665	1840	Shale & Lime	3257-3258 85 BW/D
1840	1920	Lime & Shale strks.	3261-3270 Hole full of water.
1920	1950	Lime	
1950	1975	Shale & Lime	
1975	2090	Shale & Lime strks.	
2090	2140	Lime & Shale	
2140	2502	Shale & Lime strks.	
2502	2572	Lime - Kansas City	
2572 -	2587	Sandy Shale	
2587	2608	Lime	
2608	2621	Lime & Shale strks.	
2621	2655	Sandy Shale & Lime strks.	
2655	2971	Lime & Shale	
2971	2975	Lime - Top Miss.	
2975	3055	Cherty Lime - Miss.	
3055	3090	Lime	
3090	3137	Lime & Chert	
3137	3150	Lime	
3150	3175	Shale & Lime	
3175	3221	Lime w/shale brks.	
3221	3250	Shale w/lime strks.	
3250	3257	Shale & Lime	
3257		Total Depth.	

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Thomas #1 well drilled for Mr. J. P. Gaty and completed February 18, 1954.

MORRISON DRILLING COMPANY, INC.

 C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS)
) ss.
 COUNTY OF BUTLER)

PLUGGING
 FILE SEC 9 122 R 25
 BOOK PAGE 90 LINE 23

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for the County and State aforesaid this 24th day of February, 1954.


 Notary Public