


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Sedgwick County. Sec. 33 Twp. 27 Rge. 2 (E) (W)
Location as "NE/CNW&SW" or footage from lines NE/C NW/4 NE/4
Lease Owner Mr. J. P. Gaty
Lease Name Dotts Well No. 1
Office Address 11 Cypress Drive, Forrest Hills, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-23 1954
Application for plugging filed Verbal 8-23 1954
Application for plugging approved Verbal 8-23 1954
Plugging commenced 8-23 1954
Plugging completed 8-23 1954
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3340 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gun Pits to bring weight up on Mud. Circulated for 30 Minutes. Set solid bridge @ 95 Ft. Cemented W/20 Sacks Cement. Filled on up with Rotary Mud to 15 Ft. Base of Cellar - Capped W/15 Sacks Cement.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morrison Drilling Company, Inc.
Address Drawer 712, El Dorado, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
John P. Gaty (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
11 Cypress Dr., Wichita Kansas (Address)

SUBSCRIBED AND SWORN to before me this 30th day of August 1954
My commission expires Dec. 12, 1955



J. Arnold Dowd
Notary Public.
STATE CORPORATION COMMISSION

SEP - 1 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 33 T 27 R 2E
BOOK PAGE 57 LINE 29

15-173-00443-00-00

WELL LOG-DOTTS #1

OPERATOR: Mr. J. P. Gaty
11 Cypress Drive
Forrest Hills
Wichita, Kansas

LOCATION: NE/C NW/4 NE/4
Section 33-27-2E
Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
Drawer 712
El Dorado, Kansas

PRODUCTION: D & A

Farm: Dotts - Well #1
Date Commenced: 8-12-54
Date Completed: 8-23-54

Total Depth: 3340' - Rotary

From	To	Formation
0	101	Cement
101	128	Lime
128	140	Sand and gravel
140	182	Lime
182	197	Shale and shells
197	260	Shale and lime streaks
260	568	Lime and shale
568	572	Red Bed
572	590	Lime and shale
590	720	Shale and lime streaks
720	1055	Shale and lime streaks
1055	1210	Shale and lime
1210	1510	Lime and shale
1510	1725	Shale and lime
1725	1785	Lime and shale
1785	1817	Shale and lime streaks
1817	1865	Lime
1865	1998	Lime and shale
1998	2006	Sand
2006	2074	Shale and sand
2074	2116	Shale
2116	2129	Lime
2129	2133	Sand - Stalnaker
2123	2153	Lime and shale streaks
2153	2205	Lime
2205	2240	Lime and shale
2240	2430	Shale and lime
2430	2472	Lime and shale
2472	2535	Lime - Kansas City
2535	2690	Lime
2690	2698	Shale and lime
2698	2887	Lime and shale
2887	2940	Shale and lime
2940	2956	Lime
2956	3007	Chert and lime
3007	3071	Lime and chert
3071	3207	Lime and shale
3207	3227	Shale and lime
3227	3236	Shale
3236	3240	Sand
3240	3248	Simpson Dolomite
3248	3319	Shale and sand
3319	3336	Sand and shale
3336	3340	Arbuckle
3340		Total Depth

PLUGGING

FILE SEC 33 T 27 R 2E
BOOK PAGE 58 LINE 29

Page -2- Well Log - Dotts #1

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Dotts #1 well drilled for Mr. J. P. Gaty, and completed August 23, 1954.

MORRISON DRILLING COMPANY, INC.


C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS)
) ss:
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for County and State aforesaid this 24th day of August, 1954.


Notary Public



My Commission Expires January 10, 1955.