



GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 16 1959  
 10-16-1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

15-163-00934-00-00

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date 10-6-59, 1959, authorized the following plugging operation:

Operator's Full Name: Davis Bros

Complete Address: 5 1/2 E 3rd Tulsa, Okla

Lease Name: Fritz Well No. A-1

Location: C NW NE Sec. 18 Twp. 10 Rge. 16 (E) (W)

County: Rooks Total Depth: 3506

Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

8 5/8" at 107' circulated with cement.

Circulate hole with heavy mud, set plug at 350', displace 20 sax cement  
through drill pipe, mud to 105', set plug and 15 sax cement, mud to 40'  
set plug, hulls and 10 sax cement.

Very truly yours,

Signed: Jewel M. Ogden  
 Conservation Division Agent