



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

15-163-20079-00-00

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 ST. CORPORATION COMMISSION
 DEC 4 1967
 1204-1967
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Flake of Woodman-Iannitti Drlg. has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Kern Drilling Co., Inc.

Complete Address: 337 Union Center Bldg., Wichita, Kansas

Lease Name: Zeigler Well No. 1

Location: SW SE SE Sec. 20 Twp. 10 Rge. 16 (E)(W) X

County: Rooks Total Depth 3260 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:
 Gun pits, circulate heavy mud, set cementing plug at 660' and displace
 100 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and
 displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
 plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
 with 2 sc cement.

Very truly yours,

Leo F. Messing
 Conservation Division Agent