

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-163-20004-00-00

Dear Sir:

Mr. Stetler of Birmingham & Bartlett Drilg has this date requested permission to plug the following described well:

Mr. Stetler guarantees payment of the plugging fee.

Operator's full Name: Birmingham & Bartlett Drilling Co.

Complete Address: 300 Kaufman Bldg. Wichita, Kansas

Lease Name: Whisman "A" Well No. 1

Location: SW SW NW Sec. 32 Twp. 10 Rge. 16 (E)(W) X

County Rooks Total Depth 3570' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Stetler was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace 20 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and displace 20 sc cement thru drill pipe, Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Bob J. Messer  
Conservation Division Agent