



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
4/19/66  
APR 19 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellinger of Knight Casing Pulling Cobas this

date requested permission to plug the following described well:

Tulsa Supply Co.,

Mr. Dellinger guarantees payment of the plugging fee.

Operator's full Name: Tulsa Supply Company,

Complete Address: Box # 924, Tulsa, Oklahoma.

Lease Name: Sturgeon Well No. 1

Location: NE-NW-SE Sec. 32 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3854 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Dellinger was instructed to plug the well as follows:

203' -- 8 5/8" Surface pipe, cement circulated.  
3854' -- 5 1/2" Production casing cemented with 100 Sx. Well  
plugged back to 3800'. Top perforations from 3786' to 3790'.

Sand well back to 3770' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540'  
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210' and dis-  
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge at 35'  
and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent