

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Merrion Burris of Chief Drilling Co., Inc., has this date requested permission to plug the following described well:Mr. Burris guarantees payment of the plugging fee.Operator's full Name: Chief Drilling Company, Incorporated,Complete Address: 905 Century Plaza, Wichita, Kansas.Lease Name: Sturgeon Well No. 1Location: SW-NE-SE Sec. 32 Twp. 9 Rge. (E)(W) 22County: Graham Total Depth 3810' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Burris was instructed to plug the well as follows:253'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 775'.Circulate hole with heavy mud. Pull DP to 1000' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

 Conservation Division Agent